BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the Work : Improvements to drains in 1st to 4th main road, 2nd cross road to 8th cross road in tatanagara in ward no. 8, kodigehalli

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	20.00	Hire charges of 100 KVA generator including operator, fuel, transportation and handling charges	Hours	630.00	
2	616.50	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH		83.16	
3	6781.50	Removing B.S Slab of Drain and stacking including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work		63.72	
4	513.75	Construction of embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300-2 complete as per specifications which includes watering charges and compaction		311.04	
5	5764.27	Refixing stone slabs of drains and pointing in C.M (1:3) including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work		78.84	
6	1017.23	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (10.0 cms thick)		794.88	
7	524.03	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km		78.97	

ಕಡಪು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....(0)
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Executive Engineer 21/12
Byatarayanapura Division
BBMP, Bangalore - 92